Item No.	Description	Qty	Unit	Unit Price	Price Extension

Optional Bid Items shall not be taken into consideration for award of this bid. However, the Port may elect to award these items if you are the lowest responsive and responsible for any of the other items in this Invitation for Bid.

1.1	36,000 BTU Air Conditioner	1	SE	$ 1095	$ 1095

SPECIFICATIONS:

BIDDING ON/REMARKS

Split-type Ductless, *Wall Mount, ✓
Condenser unit with anti-corrosion protection on housing and coils, ✓
Evaporator unit noise level less than 50dB, R-454B or R32 Refrigerant, ✓
208-230VAC, 60Hz, 1Ph, SEER=16 minimum, ✓ New Standard Seer 2
EER=Not less than 10.0, With standard wiring and piping kit, ✓ New Standard Eer 2
** Stainless Steel brackets and installation hardware, ✓
Certification from NRTL (See NOTES), ✓

Bidding On:
Brand: Hisense
Part/Model Number: AS-36UW3RKZ00 / AS-36UW3RKZHB00
Specifications: 36,000 BTU 20 Seer 220V
Date of Delivery: Available on Guam / 2 Days after PO recieved

1.2	Installation for 36,000 BTU Air Conditioner	1	EA	$ 450	$ 450

1.3 (Optional Bid Items for Line Item 1.1)

					BIDDING ON/REMARKS
[1] Five (5) Year Warranty on Compressor,	5	YR	$ 100	$ 500	✓
[1] Three (3) Year Warranty on Parts,	3	YR	$ 200	$ 600	✓
[2] Two (2) Year Preventive Maintenance (Twice –a-Year). See Footnotes	2	YR	$ 200	$ 400	✓

2.1	30,000 BTU Air Conditioner	1	SE	$ 1045	$ 1045

SPECIFICATIONS:

BIDDING ON/REMARKS

Split-type Ductless, * Wall Mount, ✓
Condenser unit with anti-corrosion protection on housing and coils, ✓
Evaporator unit noise level less than 50dB, R-454B or R32 Refrigerant, ✓
208-230VAC, 60Hz, 1Ph, SEER=16 minimum, ✓ New Standard Seer 2
EER=Not less than 10.0, With standard wiring and piping kit, ✓ New Standard Eer 2
** Stainless Steel brackets and installation hardware, ✓
Certification from NRTL (See NOTES), ✓

Bidding On:
Brand: Hisense
Part/Model Number: AS-30UW3RKZ00 / AS-30UW3RKZHB00
Specifications: 30,000 BTU 19 Seer 220V
Date of Delivery: Available on Guam / 2 Days after PO received

2.2	Installation for 30,000 BTU Air Conditioner	1	EA	$ 450	$ 450

2.3 (Optional Bid Items for Line Item 2.1)

					BIDDING ON/REMARKS
[1] Five (5) Year Warranty on Compressor,	5	YR	$ 100	$ 500	✓
[1] Three (3) Year Warranty on Parts,	3	YR	$ 200	$ 600	✓
[2] Two (2) Year Preventive Maintenance (Twice –a-Year). See Footnotes	2	YR	$ 200	$ 400	✓

Item No.	Description	Qty	Unit	Unit Price	Price Extension
3.1	24,000 BTU Air Conditioner	1	SE	$745	$745

SPECIFICATIONS:

BIDDING ON/REMARKS

Split-type Ductless, * Wall Mount, ✓
Condenser unit with anti-corrosion protection on housing and coils, ✓
Evaporator unit noise level less than 45dB, R-454B or R32 Refrigerant, ✓
208-230VAC, 60Hz, 1Ph, SEER=18 minimum, New Standard Seer 2
EER=Not less than 12.2, With standard wiring and piping kit, New Standard Eer 2
** Stainless Steel brackets and installation hardware, ✓
Certification from NRTL (See NOTES), ✓

Bidding On:
Brand: Hisense
Part/Model Number: AS-24TW3RBB00/AS-24TW3RBBDB00
Specifications: 24,000 BTU 18 Seer 220V
Date of Delivery: Available on Guam/2 Days after PO recieved

3.2 Installation for 24,000 BTU Air Conditioner	1	EA	$450	$450	

3.3 (Optional Bid Items for Line Item 3.1) — **BIDDING ON/REMARKS**

[1] Five (5) Year Warranty on Compressor,	5	YR	$70	$350	✓
[1] Three (3) Year Warranty on Parts,	3	YR	$200	$600	✓
[2] Two (2) Year Preventive Maintenance (Twice –a-Year). See Footnotes	2	YR	$200	$400	✓

4.1	18,000 BTU Air Conditioner	1	SE	$645	$645

SPECIFICATIONS:

BIDDING ON/REMARKS

Split-type Ductless, * Wall Mount, ✓
Condenser unit with anti-corrosion protection on housing and coils, ✓
Evaporator unit noise level less than 45dB, R-454B or R32 Refrigerant, ✓
208-230VAC, 60Hz, 1Ph, SEER=18 minimum, New Standard Seer 2
EER=Not less than 12.2, With standard wiring and piping kit, New Standard Eer 2
** Stainless Steel brackets and installation hardware, ✓
Certification from NRTL (See NOTES), ✓

Bidding On:
Brand: Hisense
Part/Model Number: AS-18TW3RXAC00/AS-18TW3RXADB00
Specifications: 18,000 BTU 18 Seer 220V
Date of Delivery: Available on Guam/2 Days after PO recieved

4.2 Installation for 18,000 BTU Air Conditioner	1	EA	$450	$450	

4.3 (Optional Bid Items for Line Item 4.1) — **BIDDING ON/REMARKS**

[1] Five (5) Year Warranty on Compressor,	5	YR	$70	$350	✓
[1] Three (3) Year Warranty on Parts,	3	YR	$200	$600	✓
[2] Two (2) Year Preventive Maintenance (Twice –a-Year). See Footnotes	2	YR	$200	$400	✓

Item No.	Description	Qty	Unit	Unit Price	Price Extension
5.1	12,000 BTU Air Conditioner	1	SE	$625	$625

SPECIFICATIONS:

BIDDING ON/REMARKS

Split-type Ductless, * Wall Mount, ✓
Condenser unit with anti-corrosion protection on housing and coils, ✓
Evaporator unit noise level less than 40dB, R-454B or R32 Refrigerant, ✓
208-230VAC, 60Hz, 1Ph, SEER=20 minimum, ✓ New Standard Seer 2
EER=Not less than 12.2, With standard wiring and piping kit, ✓ New Standard Eer 2
** Stainless Steel brackets and installation hardware,
Certification from NRTL (See NOTES),

Bidding On:
Brand: Hisense
Part/Model Number: AST-12UW3RGE00 / AST-12UW3RGED800
Specifications: 12,000 BTU 20 Seer R20V
Date of Delivery: Available on Island / 2 Days after PO recieved

5.2 Installation for 12,000 BTU Air Conditioner	1	EA	$450	$450	

5.3 (Optional Bid Items for Line Item 5.1)

BIDDING ON/REMARKS

[1] Five (5) Year Warranty on Compressor,	5	YR	$60	$300	✓
[1] Three (3) Year Warranty on Parts,	3	YR	$200	$600	✓
[2] Two (2) Year Preventive Maintenance (Twice –a-Year). See Footnotes	2	YR	$200	$400	✓

6.1	9,000 BTU Air Conditioner	1	SE	$575	$575

SPECIFICATIONS:

BIDDING ON/REMARKS

Split-type Ductless, * Wall Mount, ✓
Condenser unit with anti-corrosion protection on housing and coils, ✓
Evaporator unit noise level less than 40dB, R-454B or R32 Refrigerant, ✓
110-120VAC, 60Hz, 1Ph, SEER=20 minimum, ✓ New Standard Seer 2
EER=Not less than 12.2, With standard wiring and piping kit, ✓ New Standard Eer 2
** Stainless Steel brackets and installation hardware,
Certification from NRTL (See NOTES),

Bidding On:
Brand: Hisense
Part/Model Number: AS-09TW1RGE00 / AS-09TW1RGED800
Specifications: 9,000 BTU 20 Seer 110V
Date of Delivery: Available on Island / 2 Days after PO recieved

6.2 Installation for 9,000 BTU Air Conditioner	1	EA	$450	$450	

6.3 (Optional Bid Items for Line Item 6.1)

BIDDING ON/REMARKS

[1] Five (5) Year Warranty on Compressor,	5	YR	$60	$300	✓
[1] Three (3) Year Warranty on Parts,	3	YR	$200	$600	✓
[2] Two (2) Year Preventive Maintenance (Twice –a-Year). See Footnotes	2	YR	$200	$400	✓

Item No.	Description	Qty	Unit	Unit Price	Price Extension
7.1	Installation of In-Line Voltage Monitor	6	SE	$260	$1560.00

NOTES:

A. Item Nos. 1.1, 2.1, 3.1, 4.1, 5.1, and 6.1

1. Unit Cost is for purchase of the corresponding Air Conditioner with the listed accessories, and without installation.

2. Must be designed to operate with, and include, Refrigerant types R-410A, R-454B, or R-32.

3. Item to include standard pre-installation length of wiring and piping.

4. Unit must have certification with a Nationally Recognized Testing Laboratory (NRTL) such as UL, ETL, AHRI. Certification must be provided on Bid submission.

5. Documentation proof must be provided for the anti-corrosion protection of the Condenser housing and coils – whether applied by manufacturer or by awarded bidder. Protection must be applicable for coastal marine salt-spray environment.

6. * Item will be wall mount type for indoor unit, and wall or floor mount type for outdoor unit.

7. ** Item to include stainless steel brackets for outdoor units. Non-stainless steel brackets will only be accepted if the bracket material is galvanized and the narrowest section is not less than 3/16-inch thickness. All exterior mounting hardware shall be stainless steel.

B. Item Nos. 1.1, 2.1, 3.1, 4.1, and 5.1

1. Units must be designed to operate at 208-230 Volts, 60Hz.

C. Item No. 6.1

1. Unit must be designed to operate at 110-120 Volts, 60Hz.

D. Item Nos. 1.2, 2.2, 3.2, 4.2, 5.2, and 6.2

1. Bidder Installation of unit is optional and will be based on each individual Requisition order and subsequent Purchase Order.

2. Installation to be performed by certified technician(s) in accordance with established standards; and to include: proper refrigerant charge, testing and sign-off that unit operates as per manufacturer design.

3. For all installations, PAG will ensure mounting locations are clear of any interference/obstruction, and local disconnect means is available with proper power supply.

4. PAG to provide/operate personnel lift equipment for Condenser installations 8 feet above ground level. Bidder to provide its own required PPE for all installations.

5. Bidder to conduct post-cleanup of work areas for each installation.

E. Item No. 7.1

1. Bidder Installation of Voltage Monitor device is optional and will be based on each individual Requisition order and subsequent Purchase Order.

2. Voltage Monitor system shall include a Voltage Monitor compatible for voltages as specified on all Air Conditioners. A 2-Pole Contactor rated for 30 Amps having a Coil rated at 208-230VAC/60Hz will be installed for Item Nos. 1.1, 2.1, 3.1, 4.1, and 5.1. For Item No. 6.1, a 2-Pole Contactor rated for 30 Amps with a Coil rated at 110-120VAC/60Hz will be installed. All equipment for each installation shall be housed in a nonmetallic or stainless steel enclosure.